


- The Complete Decommissioning of a Chemical Engineering Building

Ed Abel and Clive Hamblin
Harwell Projects Department
Southern Division

International Conference on Nuclear Decommissioning '98,
London, 2-3 December 1998



< **Seven Years** >



B351 Life Cycle: 1950 - 1997+



Building Dimensions		Building Fabric	
Height x Width x Length	27 x 50 x 115m	Asbestos Cladding	3,500m ²
Enclosed Volume & Pit Volume	44,600m ³ & 850m ³	Amount of Concrete & Brickwork	4,000m ³ & 900m ³
Floor Area Covered by Lino	3,600m ²	Amount of Structural Steel	1,200te
Lab & Office Area	4,030m ²	Length of Ductwork	4,200m
Area of Metal Floor Plates	1,700m ²	Length of Lagged pipework	2,500m
Total Floor Area	10,351m ²	Depth of Basement	2.1m



Seven Storeys of Decommissioning

Background (i)



- Design began in 1946
- New design in 1948, built 1950-1952
- Galleries + big shielded cells & large Storage Pit
- Experimental, not Pre-production (Windscale)



Seven Storeys of Decommissioning

Background (iii)




- The Large Cells became cannibalised for the ^{233}U Pilot Plant Six
- The Pit was used for fuel cutting, breakdown & dissolution as well as highly active effluents



Seven Storeys of Decommissioning

Background (ii)



Seven Storeys of Decommissioning


Background (iv)



- Suites of cubicles contained Homogeneous Aqueous Reactors ZETR and HAZEL
- Many experiments on:
 - fission product melting
 - uranium/thorium MOX processing



Background (v)



- In the 1960s new work focused on vitrification, reprocessing, corrosion, separation technology and Na mass transfer
- Diversification into non-nuclear areas:
 - chemical processing
 - pharmaceuticals
 - desalination
 - heat transfer



UKAEA

Decommissioning Planning

- Looked at options for retaining some parts of building
- Analysed all areas for decommissioning and waste costs
- Considered mothballing with C&M and deferred decommissioning and with prompt decommissioning
- Concluded that best option was prompt decommissioning, as funding permitted



UKAEA

Reasons for Decommissioning




- A high cost building
- UKAEA split into nine businesses, six in B351
- No long term prospect of commercial sponsor(s)
- Approximately 200 RDAs to manage
- Need for co-ordination
- Site license conditions



UKAEA

The Decommissioning Programme



- Building Clearance
- FINGAL
- Mk I Gel Precipitation
- SEPP & U Evaporator
- CDFR Dissolver
- Main Active Ventilation
- Building Demolition
- Waste Management



UKAEA

Analytical Laboratory (i)



- Refurbished in 1957
- Chemical & radioactive hazards
- Dedicated ventilation
- Legacy contamination
- Asbestos in roof spaces & voids
- Unsafe hidden wiring



UKAEA

Analytical Laboratory - Work Phases

Work Phases

1st clearance & radiological surveys
Service isolations
Exposure of hidden hazards
Asbestos removal from pipe voids
Decommissioning of fume cupboards & active ventilation
Floor & wall scabbling
Cables stripped from roof voids
Asbestos removal from roof voids
Demolition (with main building)

Carried out by

Occupants, building surveyors
Building electricians, Site Services
Decommissioning contractor
Specialised contractor
Contractor from Competitive Tender
Term Contractor
Building electricians
Specialised contractor
Contractor from Competitive Tender



UKAEA

Analytical Laboratory (ii)




- Mix of in-house & competitive tender
- Archive research
- Cautious, piecewise approach to reduce risks
- Ductwork wrapped for local size reduction
- Segregation of wastes



UKAEA

Mild Steel Loop (i)



- High temperature & pressure corrosion loop
- Test sections still had Na sections from CDFR
- Isolated, but still left connected to mains
- Multiple feeds
- Directly above Na Lab
- *Marie Celeste* effect



UKAEA

Seven Storeys of Decommissioning

Mild Steel Loop (ii)



- Disconnected & drained
- Wiring stripped out (unknown feeds found)
- High current Transformer drained of PCB
- Pipework cut out with hydraulic shears (inactive trial for FINGAL work)
- Na sections removed when accessible



UKAEA

FINGAL (ii)



- FINGAL Flask, active block and γ gate removed
- Several controlled in-cell inspections + surveys
- Unproductive search of records for as-built details
- Intrusive survey from roof with cctv and telescopic β/γ probe
- Planned approach to tackle decommissioning



UKAEA

Seven Storeys of Decommissioning

FINGAL- abandoned vitrification cell (i)



- Early 1960s plant
- Used active liquors from Windscale (10^{15} Bq)
- Built into Storage Pit with shielded roof blocks
- Incidents led to cell and roof contamination
- Abandoned in mid-60s in favour of Harvest and rotary calciners



UKAEA

Seven Storeys of Decommissioning

FINGAL (iii)



- Cell contained Pb wall >2.5m high with ~800 150kg blocks
- Modular Containment built to give extra space
- Access limited to narrow corridor and 0.75m door
- Ventilation system contaminated and decrepit
- No way to deal with large quantities of LLW



UKAEA

FINGAL (iv)



- Mobile Filtration Unit (4000 cfm) fitted to RDP
- HISO facility built in Pit using 50 ton crane
- Modified stacker truck and folding cranes used to aid manual handling
- Improved tooling, audio & cctv communications



UKAEA

Mkl Gel Precipitation Lab (i)



- Used to prepare U/Th spheres for fuel studies
- Simple construction, could still use building ventilation system
- additional hazards of nitric acid, organic solvents and ammonia
- adjacent structures and equipment contaminated



UKAEA

FINGAL & Pit Concrete



- Cell decontamination attempted and concrete sampled (hollow drill)
- Roof blocks removed, cored & decontaminated
- Support walls broken down and disposed of
- Wall bulk removal trials
- Remaining areas cleaned and scabbled/scarified



UKAEA

Mkl Gel Precipitation Lab (ii)




- Was U storage area and High Temperature Lab
- Catch tray floor and main wall (14m x 14m) contaminated
- Temporary walls hid old contaminated items
- Remote low-loss cabled cctv used to monitor work
- Cherry-picker for survey



UKAEA

SEPP & the Uranium Evaporator (i)



- Studies of U recovery during fuel reprocessing
- 80m³ Cubicle with several 12m tall extraction columns over five floors
- Mixer Settler Cubicle
- Evaporator Plant to concentrate uranyl nitrate
- Contaminated TBP/OK



UKAEA

SEPP & the Uranium Evaporator (iii)




- No easy disposal route for contaminated solvents
- Contaminated pipework packed into larger vessels and placed in HISOs
- Solvent drained to two SEPP tanks until process options determined
- Ion-exchange process developed for TBP/OK



UKAEA

SEPP & the Uranium Evaporator (ii)



- Competitively Tendered
- RPE + safety helmets in cubicles
- Working at height
- Confined spaces
- Corrosive chemicals
- Evaporator contained & vented to building ducts



UKAEA

The CDFR Dissolver (i)




- Studies of dissolution of spent fast reactor breeder fuel in various dissolvers
- 100m³ ventilated cubicle with off-gas treatment
- Large storage tanks for liquors (conc. HNO₃, NaOH, uranyl nitrate)
- Substantial stainless steel dissolver



UKAEA

The CDFR Dissolver (ii)




- Competitively Tendered
- “POCO” completed by contractors - liquors analysed and disposed of
- Decommissioning used cubicle containment + new ventilation
- Most materials clean
- In situ plasma cutting of main dissolver



UKAEA

Main Active Ventilation System (ii)



UKAEA

Main Active Ventilation System (i)



- Mainly mild steel ducts (~4km and up to 3m x 3m) through building to two Plant Rooms
- Most with HEPA filters
- Competitively Tendered
- Runs tented to allow safe dismantling
- Old ducts insulated with cork and asbestos cement



UKAEA

Main Active Ventilation System (iii)



- All ductwork, fans and housings size reduced in special facility in B351
- Decontamination used when beneficial
- Cold cutting techniques developed and used (band saws, nibblers, etc)
- Flat-packed waste sent to B351 HISOs for disposal



UKAEA

Building Demolition - West Wing (i)



- Used as "safe" trial for main building
- Services disconnected & asbestos removed
- All equipment, cubicles, floor coverings, partitions, fume cupboards and duct-work removed
- Floor plates and joists surveyed, decontaminated and removed



UKAEA

Building Demolition - Delay Tanks (i)




- North Delay Tank Complex to green field
- High pressure water jetting removed most of contamination
- Up-ended tanks allowed non-confined space decontamination work
- Mass size reduction of tank by hydraulic shear



UKAEA

Building Demolition - West Wing (ii)



- Roof demolished
- Asbestos wall cladding manually stripped
- Structural steel removed
- Proved need to lift plates
- Proved benefits of long range surveillance cctv for management control
- Proved benefits of long reach deployment of man-cages



UKAEA

Building Demolition - Delay Tanks (ii)



- South Delay Tank Pit Complex totally cleared, eventually backfilled with B351 rubble and capped
- Tanks also cleaned (by HP water jetting and selective flame cutting) to free release and special precautions burial levels
- Pump house demolished



UKAEA

Main Building Demolition (i)



- Competitively Tendered
- Environmental Impact Assessment (B351 was 11m from Site Boundary)
- Vibration, noise and dust control measures in ITT
- Surveillance cctv installed on masts, relayed to new Project Offices close to site



Main Building Demolition (iii)



- Main steel/concrete structures collapsed using wrecking ball and progressive cutting of steel
- Continuous radiological surveys and environmental monitoring
- Demolition completed in August 1997 but basemat and capped Pit on C&M



Main Building Demolition (ii)



- Demolition began in April 1997 with brick built Office and Analytical Lab Wings
- Storage Pit backfilled with this rubble to allow close, load-bearing access to North Side of building
- Asbestos cement panels removed from cladding frames via scaffolding and cages



Main Building Demolition (iv)



Waste Management (i)



- Radiation monitoring and sampling rigorously applied to help segregation and minimise volumes
- Waste fingerprints determined before work
- gross activity with β analysis and α - and γ -spectrometry identified isotopes and checked compliance for Drigg



Waste Management (iii)



- Materials recycled on the B351 site (backfill of ducts and Delay and Storage Pits)
- Chemical waste sentenced through AEAT's HDS
- Non-hazardous wastes sold or to landfill via skips
- LLW volumes close to estimates but decontamination techniques failed to scale up adequately



Waste Management (ii)



- 200l bins (compactable), HISOs (non-compactable)
- ~1 tonne of nuclear material (U + Th) as contact handled ILW
- FINGAL block as 540l ILW in own flask
- 1000's of chemical analyses on ~5ml to tonne quantity bulk materials
- Audited disposals



LLW & ILW Disposals

Financial Year	Estimate from 1991 Plan	LLW (m ³)		(Including HISOs)	ILW (litres)	
		Actual	Plan		Actual	Plan
1990/91	-	10.5	-	-	540	-
1991/92	46.7	32.0	-	-	0	-
1992/93	26.5	23.6	-	-	1,227	-
1993/94	33.0	54.6	18.0	18.0	30	-
1994/95	262.7	239.6	133.5	133.5	0	-
1995/96	27.9	89.5	58.5	58.5	2,450	-
1996/97	135.0	157.1	133.2	133.2	100	-
1997/98	75.0	91.4	44.4	44.4	100	-
TOTAL	606.80	698.3	387.6	387.6	3,907	-



Conclusions (i)

- B351 was complicated, contaminated and large
- Safe and successful decommissioning to plan and within budget
- Careful planning by resident management and direct control of all tasks minimised problems, reduced risks and costs
- Consistent standard of work was the result of continuity of the management team and a common approach to contractors

Conclusions (iii)

- CCTV used where areas could not be easily observed - plant/duct inspections and inside containments
- Installed, controllable surveillance systems gave managers direct views of work in progress and allowed progress to be noted safely from a distance
- Techniques developed and used in this project and the lessons learnt have been applied to other UKAEA projects with equal success

Conclusions (ii)

- FINGAL drove choice of HISOs but this proved to be the best solution for B351 waste - controlled size reductions for ventilation and easy cross-site transfers
- All tasks subject to rigorous safety assessments and controlled by Method Statements and Permits to Work
- All Contractors underwent site and building specific training
- There were no serious incidents or accidents

The Team

